

Risk Management Services

A GREENCAP CONSULTING COMPANY

NOEL ARNOLD & ASSOCIATES PTY LTD
 A.B.N. 76 006 318 010
 A.C.N. 006 318 010
 Level 2, 11 Khartoum Road,
 North Ryde, NSW 2113 Australia
 Phone: (02) 9889 1800
 Fax: (02) 9889 1811
 Email: sydney@noel-arnold.com.au
 www.noel-arnold.com.au

30 November 2012

Our Ref: J111804-S3; C107605
 J111804-S3 Asbestos Air Monitoring Summary Report 28 Sept - 30 Nov 2012

Martin Gear
 Project Manager Aggregates
 Hanson Construction Materials
 Email address: martin.gear@hanson.com.au

Re: Asbestos Air Monitoring Results for the Period from 28th September to 30th November 2012 – East Guyong Quarry Project

This letter presents the summary of the asbestos air monitoring results at the East Guyong Quarry Project site located off the Mitchell Highway, East Guyong NSW for the period between Friday 28th September and Friday 30th November 2012.

The asbestos air monitoring was undertaken by National Association of Testing Authorities Australia (NATA) approved personnel and the filter samples were analysed in our NATA-accredited laboratory in accordance with the Safe Work Australia's Guidance Note on the Membrane Filter Method for Estimating Airborne Asbestos Fibres 2nd Edition [NOHSC:3003 (2005)].

A summary of the air monitoring results for the period between Friday 28th September and Friday 30th November 2012 are presented in a tabular format below.

Date	No. of Air Samples	Summary of Results	Any Exceedances of QL Note 1 (Yes or No)	Any Exceedances of AIAc Note 2 (Yes or No)
16/10/2012	4	<0.01	No	No
18/10/2012	12	<0.01	No	No
22/10/2012	5	<0.01	No	No
23/10/2012	5	<0.01	No	No
30/10/2012	8	<0.01	No	No
31/10/2012	6	<0.01	No	No
16/11/2012	6	<0.01	No	No
19/11/2012	6	<0.01	No	No
20/11/2012	6	<0.01	No	No
21/11/2012	5	<0.01	No	No


Air Monitoring (Mitchell Highway road construction and associated works)

Note 1 "Quantification Limit" (QL)
 Note 2 "Asbestos Impact Assessment Criterion" (AIAc)

The **air monitoring results** for asbestos conducted for 10 days during the period between Friday 28th September and Friday 30th November 2012 at the East Guyong Quarry site during the Mitchell Highway road construction works to the access road no.3410 were less than detection limit of the method (i.e. < 0.01 fibres/ml) and also below the QL and AIAc of 0.01 fibres/ml.

In summary, no air monitoring results exceeded the QL or AIAc.

SIMON BUTTERFIELD
Occupational Hygiene Manager



NOEL ARNOLD & ASSOCIATES PTY LTD

Yours sincerely,

November 2012

